



SUNSHINE COAST REGIONAL DISTRICT

Question and Answers # 4

Request for Proposal No. 2536503

Watermain Replacement North Pender Harbour

Date: November 19, 2025

Item No.1

Question: Are pipe to pipe or pipe to fitting mechanical joint restraints required for this project?

Answer: Joint restraints are not required for this project unless otherwise noted. Thrust restraint is to be achieved via cast in place concrete thrust blocks.

Item No.2

Question: Does Ductile iron pipe need pipe to pipe restraints?

Answer: No, see response to Item 1 above.

Item No.3

Question: Is Spray foam insulation required?

Answer: Please bid as per contract documents, rigid insulation as specified as shown on Sheet C302.

Item No.4

Question: Are we to assume that Permanent Pavement Restoration is to allow for 100mm Asphalt thickness?

Answer: Yes. Please refer to Q&A 3 Item No. 16 and 17.