



SUNSHINE COAST REGIONAL DISTRICT

Question and Answers #2

Request for Proposal No. 2661301

Electrical Services: Natatorium and Interior Lighting Replacement

Date: March 6, 2026

Item No.1

Question: We are seeking approval for a proposed alternative from a supplier please see the attached document (Prepared by Husam Dawoud -Mac's ii Design Team), can you please advise if the alternative is acceptable.

Answer: Selections for M15, W15, M20, W20, F, G, L Option-1, and N are probable alternatives. Selections for B, L Option-2, Y for both options and Q would not be accepted for the following reasons:

- B: No clear IP65 or equivalent rating.
- L option 2: No clear IP65 or equivalent rating, colour tune not specified.
- Y: Both options are not IP65 rated, both options' lumens are out of range, and both options' colour tunability is not as required.
- Q: Lumens are too high, and the CRI is too low compared to the specifications.

All these submittals would have to be resubmitted after the project is awarded, and they will be reviewed and subject to approval by the consultant and Regional District.

Item No.2

Question: Are paint colors supplied or is it just a matter of color check to get as close as possible?

Answer: Most paint colours are available and can be provided upon request. If a colour is not available a colour match is acceptable.

Item No.3

Question:

- a) Could we get some clarification on the mock ups?
- b) Is this a matter of installing one and having it checked?
- c) Is the intent that one be installed offsite for approval?

d) Do you require a mock up for every fixture type?

Answer:

- a) Yes, before installation, the mock-up is to be confirmed by the consultant or Regional District before finishing work.
- b) Yes, the Regional District will have an example of each type to check if it meets the Regional District's needs.
- c) Installing on-site for a mock-up is preferred.
- d) Yes.

Item No.4

Question:

- a) Do you require every fixture to have its own warranty tag?
- b) Does each one have to be individually signed by inspector?

Answer:

- a) Yes.
- b) Contractor to confirm with AHJ inspector requirements.

Item No.5

Question: With regards to cleaning, looking for clarification on extent of cleaning for each area.

Answer: Areas are to be cleaned of all dust and debris resulting from the lighting replacement work. Areas should be left in a similar condition as they are found at the start of the work.

Item No.6

Question: Are new cables, junction boxes, knockout fillers, cover plates, etc. in the natatorium needing to be painted to match?

Answer: Yes.