



## SUNSHINE COAST REGIONAL DISTRICT

Question and Answers #2

Request for Proposal No. 2637002

Watermain Replacement Reed Road

**Date: April x, 2026**

### **Item No.1**

**Question:** Please clarify the discrepancy between the Native Backfill quantity shown in the Schedule of Quantities/Pricing Table versus the drawings for the Reed Road Watermain Replacement. The pricing table indicates 220 m<sup>3</sup> for "Watermain 300mm CI with Native fill," while our drawing takeoff indicates approximately 418 m<sup>3</sup>.

**Answer:** The drawings show where we expect to be able to use the native material, some of the material may not be useable if it does not meet testing, the estimation is that more Imported fill will be required, this is why we have only estimated that 220 lineal meters of pipe will be installed with native material.

### **Item No.2**

**Question:** Could you please confirm the dimensions of the air valve chamber?

**Answer:** ARMTEC AE T266 or approved equivalent as detailed in Standard Detail Drawing D1 see - W2E and W6. An example T266 Service Box – Complete shown below.